
JVWTP



Contractor Pre-Bid Meeting

March 26, 2025

Approx. Time Discussion Topic 2:00 PM Welcome/Intro/Purpose 2:10 PM **Process Areas/Facilities Overview** 2:30 PM Break **Meeting Agenda** 2:45 PM Site Walk JVWCD Attendees: Stephen Blake Contractor Attendees: Design Consultant Attendees: Alan Domonoske Austin Peters Stetson Bassett Brad Buswell Michal Lieberman Carollo



Project Overview: Project Objective




Prepare the filtration and chemical systems at the JVWTP to reliably provide 268 MGD of gross treated water capacity.


Purpose and Goals


- Introduce major project elements and facility areas
- See the site
















Chemical Feed Upgrades (PEC)

 Cationic polymer (PEC): New bulk storage, day tank, and metering will be installed in the new polymer area. An existing bulk storage in the Primary Coagulant Building currently utilized for PEC will be repurposed for Primary Coagulant.

Areas: 69, 71








Chemical Feed Upgrades (PEA)


• Anionic polymer (PEA): New PEA batching, storage, and metering systems will be installed in the existing Filter Building. New dosing locations will be installed in the Flocculation Basins. Existing PEA system, on the third floor of the Administration Building, will be connected to this new system as a standby system.

Areas: 69










<section-header><section-header><section-header><section-header><section-header><text><text><image>

Chemical Feed Upgrades (Fluoride)

• Fluoride: Existing chemical piping and utility water piping in the yard to be replaced with new piping. Small piping modifications inside existing building to accommodate new connections.

Areas: 66



16

<text><text><text><text><image>

Electrical Improvements

- Installation of new emergency power generator. (Area 55)
- Contractor shall employ Steve Anderson/APCO for PLC and SCADA programming (Per Specification 01110/17050)
- JVWCD is building the RTUs.(Per Specification 17050)


18

Electrical Improvements

1. Re-purpose the 480V power feed to the Culinary Pump Station for the new Chlorine and Caustic Soda Buildings.

2. Revise the medium voltage circuit along 3200W to re-power the Culinary Pump Station from Sectionalizer 1.

3. Re-work the Alternate Plant Feed on the north side of the Filter Building to repower the upsized blower motors.





Misc. Civil and Structural Improvements

- Civil yard and grading improvements.
- Utility modifications to support the overall work.
- Repair and reconstruction of existing improvements affected by the Work, and incidentals for complete and usable facility.
- Installation of a canopy over the entrance walkway.



20






Shutdown Limitations

Plant shutdowns for construction activities are limited according to 01140

Type of Shutdown	Allowed ⁽¹⁾	Additional Requirements	Types of Activities that may be Performed
Complete Plant	Nov 1 - Feb 28 Only: One 120-day shutdown each winter. Oct - 1 - Oct 31 Only: One 2-day (48 hours) shutdown. Mar 1 - Mar 31 Only: One 2-day (48 hours) shutdown.	None.	Chemical feed tie-ins for new chlorine, caustic, and PAC. Chemical feed tie-ins for primary coaguidant, PEC. Chlorine dioxide tubing replacement to raw water meter vault. Cutting new filter effluent piping into Filters 1-6 and into FE channels for Filters 7-16. FTW bein MH connection. BW yard piping modifications. New BW supply north nat south control valves, BWS valve, flowmeter.
Partial Plant	Oct 15 - Apr 15 Only: Up to 3 months in duration.	One week is needed to switch to half plant operations or change which half the plant is in operation. No shutdowns allowed May 15 - Sep 15.	Work on either north or south filters. PEA filter feed points. Replace chlorine dioxide tubing to filter inlet channel. Demo filter inlet weirs. Replace filter inlet and waste washwater valves. Replace filter offluent piping upstream of effluent and FTW valves. Replace filter offluent Piping upstream of effluent and FTW valves. Replace individual filter BW vales (after new BW supply N and S control valves are installed).
Unit Process	Up to 1 month in duration.	Shutdowns must be separated by 1 week. No shutdowns allowed May 15 - Sep 15.	 Minor modifications/adjustments within a filter box. Installing PEA piping in a flocculation basin.
Support Facilities	Up to 4 hours in duration, unless mutually agreed that a longer duration is tolerable.	Shutdowns must be separated by 1 week. No shutdowns allowed May 15 - Sep 15.	 Backwash system modifications. Cleaning/emptying of existing PEC storage tank to convert to use with primary coagulant.



- · No or equal approvals will be done before the bid
- Any answers to questions given today are not official
- All questions must be submitted formally and will be addressed via addenda.

